

TRI-COUNTY HEALTH DEPARTMENT  
 ENVIRONMENTAL HEALTH DIVISION  
 NOTICE OF ADDITIONAL FEES FOR INDIVIDUAL SEWAGE DISPOSAL SYSTEM  
 PER TRI-COUNTY BOARD OF HEALTH RESOLUTION OF July 1, 1995

NOTE: PERMIT OR FINAL APPROVAL WILL NOT BE ISSUED UNTIL ALL APPLICABLE FEES HAVE BEEN PAID.

OBJECT CODE	ADDITIONAL SERVICE	TOTAL
506000	Plan Review by Department Engineer: _____ hour(s) @ \$50.00/hour Date(s) Performed: _____	_____
507500	Staff Consultation: _____ hour(s) @ \$30.00/hour Date(s) Performed: _____	_____
506500	Additional Site Visit(s): _____ Visit(s) @ \$50.00/visit Date(s) Performed: _____	_____
507000	Additional Inspection(s): <u>1</u> Inspection(s) @ \$50.00/inspection Date(s) Performed: <u>11-5-02</u>	<u>50.00</u>
<b>TOTAL FEES DUE:</b>		<u>50.00</u>

\*\*\*\*\*

File Number \_\_\_\_\_ Permit Number (if issued) 2002-07-1022684  
 Property Owner Light House Custom Homes Phone # 720-488-1804  
 Address/Legal Description of Property Served by System: 2950 Castle Butte Dr.  
 City Castle Rock State CO Zip 80104

\*\*\*\*\*

The fee of 50.00 must be paid at the following office: (office address stamp)

TRI-COUNTY HEALTH DEPARTMENT  
 101 Third Street  
 Castle Rock, CO 80104  
 303-663-7650

John Kleckner  
 Environmental Health Specialist

11/05/02  
 Date Completed

CK # 3024  
11-15-02  
 Date Paid



Test Pit Required  
Applicant Notified  
Yes \_\_\_\_\_ No \_\_\_\_\_



## TEST PIT "WAIVER" WORKSHEET

Address of Proposed ISDS: 2950 Castle Butte Drive

Engineer who submitted soils and percolation test: Castle Rock Eng.

If the system is engineered for the following conditions, a test pit may be waived:

1. When the average percolation rate is slower than one (1) inch in sixty (60) minutes or faster than one (1) inch in five (5) minutes.
2. Where the maximum seasonal level of the groundwater table is less than four (4) feet below the bottom of the proposed absorption system.
3. Where bedrock or Dawson sand exists less than four (4) feet below the bottom of the proposed absorption system
4. Where the ground slope is in excess of (20%) percent.

If the system is **not** engineered for reasons 1-4 above, the EHS **must** consider the following criteria to determine if a "test pit" is necessary. A "yes" answer to any question will require a test pit, except as noted on question #1.

1. Is one or more of the **individual** test hole percolation rates greater than 60 minutes per inch, but the **average** percolation rate (for all test holes) is less than 60 minutes per inch?

Yes \_\_\_\_\_ No

For example: Hole #1: 24 mpi; Hole #2: 16 mpi; Hole #3 90 mpi; Average: 43

If the owner agrees to have the system engineered for the highest percolation rate, the test pit can be waived.

2. Did the engineer answer "yes" to the question; "Did water remain in the hole after the overnight soaking period", and the average percolation rate is less than 60 mpi?

Yes \_\_\_\_\_ No

3. This question only applies to soils classified as SW (sand, well graded), SP (sand, poorly graded). Did the engineer report a blow count of 20/12 (twenty blows to drive the sampler 12 inches) or more, but does not indicate that bedrock is present?

Yes \_\_\_\_\_ No \_\_\_\_\_ NA

4. Did the engineer indicate that bedrock or groundwater are present within 8 feet of the surface?

Yes \_\_\_\_\_ No

5. Did the engineer indicate that the soils are "wet" and not indicate that groundwater is present?

Yes \_\_\_\_\_ No

TEST PIT REQUIRED? YES \_\_\_\_\_ NO

EHS: Don Bussekk EHS Number: 813 Date: 8-7-02

ISDS INSPECTION

Partial

Final

Date: 11-1-02

Time: \_\_\_\_\_

Date Ready: 11-1-02

Permit #: \_\_\_\_\_

Address of Property: 2950

Castle Butte Dr.

Installer: Cline Contractors


Phone #: 303-663

Chambers: B or T # Units 44

Schmidt 1250  
Engi? \_\_\_\_\_ Sq. Ft

Insp. Waived? Y N By: \_\_\_\_\_

Need Klarrens approval of  
Lift Station Application. bd  
11-1-02



# Tri-County Health Department

Serving Adams, Arapahoe and Douglas Counties

Richard L. Vogt, M.D.  
Executive Director

## CERTIFICATION OF INDIVIDUAL SEWAGE DISPOSAL SYSTEM

This certifies that Individual Sewage Disposal System (ISDS) at  
2950 Castle Butte Drive Castle Rock CO 80104  
Subdivision: Keene Ranch County: Douglas  
has been permitted and installed in compliance with Tri-County Health  
Department Regulation Number I-96. A file for the ISDS will be kept in  
our Castle Rock office.

### SUMMARY OF INFORMATION

The permit number for the system was: 2002-07-022624

The soils and percolation test was performed by: Castle Rock Engineering Inc

The design engineer for the system was: No Design Engineer Used

The system was installed by: Cline Utility Contractors Inc

The system consists of:

- 1,000 gallon septic tank
- 500 gallon dosing tank
- 44 chambers
- 800 square foot absorption area.

The system is sized for 4 bedrooms. If additional bedrooms are  
added, an expansion may be necessary.

### Maintenance Requirements:


The septic tank must be pumped and inspected every 4 years

If the septic or dosing tank is equipped with an effluent filter, the  
filter must be cleaned annually


If the system has alternating beds or is a drip irrigation system, beds or  
zones must be rotated annually


Additional maintenance requirements may apply. Refer to the operations  
manual or engineer's report for specific requirements.

Signature:

  
KLECKNER, JOHN T.

Date:






Onsite System  
As-Built  
Drawing

Property Address 2950 Castle Butte Dr.  
Permit # \_\_\_\_\_  
Date System Completed 11/01/02  
Installer's Name Cline Utility Cont. Inc.  
Installer's License # \_\_\_\_\_  
Installer's Address and Phone P.O. Box 792  
Franktown, CO 80116 303 663-6565


Lot #141

### Lighthouse Custom Homes


A-C = 130'  
B-C = 121'  
C-D = 12'  
D-E = 8'  
E-F = 65'  
F-G = 20'  
G-H = 48'



44 Chamber  
in bed  
800 sq. ft.




plastic 500 gal. Schmitt  
with 1/2 hp pump



2002-07-

PERMIT # 1022624



**TRI-COUNTY HEALTH DEPARTMENT**  
Serving Adams, Arapahoe and Douglas Counties

APPLICATION TO  
 INSTALL(255)  REPAIR(256)  EXPAND(256)  
\$300 \$250 \$250  
AN INDIVIDUAL SEWAGE DISPOSAL SYSTEM

ADDRESS OF PROPERTY SERVED BY PROPOSED SYSTEM:

2950 CASTLE BUTTE DR Castle Rock  
Street Address City  
80104 Douglas  
Zip Code County

Parcel NE 1/4 Sec NW 1/4 Sec Section 30 Township 8S Range 67W Lot 141 Block —  
Legal Description (if no street address)  
KEEDE RANCH 3  
Subdivision Name Filing (if applicable)

If GPS Information Available/Obtained: Longitude \_\_\_\_\_ Latitude \_\_\_\_\_ Elevation \_\_\_\_\_

Property Owner:	
Name	<u>Light House Custom Homes</u>
Address	<u>Box 708</u>
City, State	<u>LITTLETON CO</u>
Zip	<u>80160</u>
Phone	<u>720 488-1804</u>

Applicant: <u>SAME</u>	
Name	_____
Address	_____
City, State	_____
Zip	_____
Phone	_____

Systems Contractor: R. V. S. TCHD Use Only: License # \_\_\_\_\_

Soils/Percolation Test Engineer: Castle Rock Engineering Job # 02-2730

TCHD Use Only: FSE # \_\_\_\_\_

Design Engineer (if applicable) \_\_\_\_\_ Job # \_\_\_\_\_

TCHD Use Only: FSE # \_\_\_\_\_

Is this to be an Engineered System?  Yes  No

Lot Size: 7 A.

Is lot marked and are perc holes staked?  Yes  No

PROPOSED FACILITY:

Single Family (SF)  Multi-Family (MF)  Commercial (CM)  Other (OT) \_\_\_\_\_

WATER SUPPLY:

On Site:  Yes  No Community Water  Yes  No If Yes, Supplier \_\_\_\_\_

Continued on back

PERMIT # 1022624

**SINGLE FAMILY RESIDENTIAL GENERAL INFORMATION:**

Number of Bedrooms 4 Basement:  Full (F)  Walkout (W)  Partial (P)  None (N)

Basement Plumbed:  Yes  No

Are Additional Bedrooms Planned?  Yes  No Are the premises within 400 ft. of a sewer line?  Yes  No

Is property within boundaries of a sewer district?  Yes  No

If Yes, name of sewer district \_\_\_\_\_

**COMMERCIAL GENERAL INFORMATION:**

Type of Business: \_\_\_\_\_

TCHD Use Only: SIC Code \_\_\_\_\_

Number of Employees: \_\_\_\_\_

Design Flow > 3,000 Gallons/Day  Yes  No

If Yes, has Site Approval been given from CDPHE?  Yes  No

(Note: Permit cannot be issued until site approval is given from CDPHE)

Floor Drains  Yes  No

EPA Shallow Injection Well Inventory Request Form Completed  Yes  No

Date Paid: 8-6-02 Received By: [Signature]

Payment Type:  Cash

Check (# 1275)

Charge: \_\_\_\_\_

Other \_\_\_\_\_

Amount Paid \$ 300.00


Applicant's Name WALT SLAGEL  
Please Print

Applicant's Signature [Signature]

Date Aug 6-02

- |   |   |  |   |
|---|---|--|---|
| <input type="checkbox"/> Aurora<br>15400E. 14 <sup>th</sup> Place, Ste. 309<br>Aurora, CO 80011<br>303-341-9370 | <input type="checkbox"/> Castle Rock<br>101 3 <sup>rd</sup> Street<br>Castle Rock, CO 80104<br>303-663-7650 | <input type="checkbox"/> Commerce City<br>4201 E. 72 <sup>nd</sup> Avenue, Ste. D<br>Commerce City, CO 80022<br>303-288-6816 | <input type="checkbox"/> Englewood<br>4857 S. Broadway<br>Englewood, CO 80110<br>303-761-1340 |
|---|---|--|---|





# Tri-County Health Department

Serving Adams, Arapahoe and Douglas Counties

Permit # 2002-07-022624

**PERMIT TO CONSTRUCT  
AN INDIVIDUAL SEWAGE DISPOSAL SYSTEM**  
Tri-County Health Department  
7000 East Bellevue Avenue Suite 301  
Englewood, Colorado 80111

Richard L. Vogt, M.D.  
Executive Director

Owner **LIGHT HOUSE CUSTOM HOMES**  
Location: **2950 Castle Butte Drive Castle Rock CO 80104**  
Subdivision: **Keene Ranch County: Douglas**

=====  
**System Requirements:**

Tank Size: 1250 Gallons

**Design Requirements:**

**Trench System:**

**Bed System:**

Min. Disposal Area in Sq. Ft.	1,000	1,300
Number of Chambers (Except EQ36)	36	44
Number of Chambers - EQ36 ONLY	44	64
Max Depth of Disposal Area: (Bed or Trench):	56.00 inches	
Min Depth of Disposal Area: (Bed or Trench):	22.00 inches	

**\*\*Maximum depth of chambers shall not exceed 48 inches\*\***

=====  
A Permit to **CONSTRUCT** shall expire **ONE YEAR** from the date of issuance unless extended to a fixed date upon request by the Applicant and approved by the Tri-County Health Department.

This Permit Expires: 08/09/2003

Issued by: Kleckner, John T., John Kleckner EHS

Reviewed by: Gary L. Haul  
Tri-County Health Department on August 12, 2002

**OWNER MUST MAKE SURE THAT HIS/HER ENTIRE WASTE DISPOSAL SYSTEM REMAINS OPEN FOR INSPECTION UNTIL IT HAS RECEIVED APPROVAL BY TRI-COUNTY HEALTH DEPARTMENT. TRI-COUNTY HEALTH DEPARTMENT CANNOT ASSUME RESPONSIBILITY IN CASE OF FAILURE OR INADEQUACY OF A WASTE DISPOSAL SYSTEM BEYOND CONSULTING IN GOOD FAITH WITH THE PROPERTY OWNER.**

Permit Fee: 300.00 Payment Method Check #1275  
Received By: Dutton, Elizabeth on 08/06/2002  
( ) Owner Copy ( ) Bldg. Dept. Copy ( ) Installer Copy ( ) H.D.

To:  
Warren  
Brown



# Tri-County Health Department

## APPLICATION TO INSTALL A LIFT STATION

ADDRESS OF PROPERTY SERVED BY PROPOSED LIFT STATION:  
2950 Castle Butte Dr. - Keene Ranch Subdivision  
Systems Contractor: Cline Utility Cont. Ins. Date Submitted: 10-31-02  
Phone Number: 720 635-1756 Fax Number: 720 733-8126  
Reason for Installing Lift Station: system up hill from house

Pump manufacturer and model: Little Giant 95 1/2 hp

Elevation (height) difference between bottom of dosing tank and bottom of absorption area distribution pipe (feet) 8'

Dosing tank size in gallons (minimum allowable size is 300 gallons): 500 gallon

Is dosing tank a two-compartment tank? no  yes  no  
Note: Adequate septic tank capacity, as specified in the installation permit, must be provided in addition to the dosing tank.

Manufacturer of dosing tank: Potronics Mfg. Inc. - station installed for sonoran homes 2 weeks ago ☺

Distance from dosing tank to absorption area (feet): 40'

Size of supply line pipe from pump to absorption area (inches): 2"

### General Requirements for All Lift Stations

- A "quick disconnect" shall be provided in supply line from the pump, to allow for removal of pump.
- Liquid level controls shall be provided to start and stop the pump in addition to an alarm float switch.
- A "high water" alarm shall be provided inside the dwelling, garage or building to signal malfunction of the lift station pump or controls.
- Provision shall be made, to prevent siphoning of effluent within the absorption system back to the dosing tank, and to drain effluent within the supply line back to the dosing tank or to the absorption area between doses, to prevent freezing of the effluent within the supply line. Automatic air release valves shall be installed at high points in the pressure line where necessary to prevent air locking.
- Pumps shall be installed at least four inches off the floor of the tank.
- All electrical work, equipment, and material shall comply with the requirements of the National Electrical Code in force on the effective date of this application, or those revisions of said Code as are adopted by the State Electrical Board.

Reviewed and Approved by: [Signature] Date: 11/1/02

**FINAL VISIT WORKSHEET**

Permit Number: 2002-07-022624

Date Printed: August 12, 2002

Property Location: 2950 Cstle Butte Drive Lot 141

County: Douglas

Owner: Light House Custom Homes

System Installer#: Clines (This will appear on the Certification Letter)

System sized for 4 Bedrooms

**SITE INFORMATION:**

Keys for completing information on installed tanks:

Usage (D)osing (T)reatment (V)ault

Tank Type: (C)oncrete (PT)Polyethelene (FG)Fiber Glass

**TANK INFORMATION**

Number of Tanks Installed: 2

Tank Size in gallons and Usage:

Tank 1:

Size 1000 Use (D)  (T)  (V)   
 Type  (C) (PT) (FG) T's or Baffles (T)  (B) Effluent Screen Y  (N)

Tank 2:

Size 500 Use  (D) (T)  (V)   
 Type (C)  (PT) (FG) T's or Baffles (T) (B) Effluent Screen Y  (N)

Tank 3:

Size \_\_\_\_\_ Use (D) (T) (V)   
 Type (C) (PT) (FG) T's or Baffles (T) (B) Effluent Screen Y N

Secondary Treatment System Y  (N) If yes, type: (circle one)

Sand Filter (SF) Constructed Wetlands (CW) Trickling Filter (TF)

Aerobic System (AS) Recirculating Sand Filter (RSF) Other (OT)

**Final Treatment Type:**

Bed (BD) Mound (MD) Trench (T)  
 ET (ET) Pond (PD) Sand Filter (SF)  
 Bed (Chambers)  (BD-CH) Trench SB-2 (TR-SB) Drip Irrigation (DR)  
 Trench (Chambers) (TR-CH) Other (OT)  
 Area Size (s.f.) 300 If Chambers Used, # 44 ET Lined Y N

**Method of Waste Water Application:**

Dosed w/Pump  (DP) Dosed w/Siphon (DS) Gravity (GR)  
 Uniformly Dosed w/ Pump (UDP) Uniformly Dosed w/ Siphon (UDS)

\*\*\*Continued on Next Page\*\*\*

FINAL VISIT WORKSHEET

Permit Number: 2002-07-022624

Date Printed: August 12, 2002

RECORD OF FINAL VISITS:

(It is important to record any extra visits for billing purposes)

Visit 1 Date 11/01/02 By (EHS #) 1555

Visit 2 Date 11/05/02 By (EHS #) 1555

Visit 3 Date \_\_\_\_\_ By (EHS #) \_\_\_\_\_

Visit 4 Date \_\_\_\_\_ By (EHS #) \_\_\_\_\_

System Engineer Inspection Y  N Date \_\_\_\_\_

Design Engineer # \_\_\_\_\_ (This will appear on Certification Letter)

FINAL SITE VISIT COMMENTS:

11/01 Pump station not finished  
11/05 Inspected pump station.  
Waiting for AS-Built J.K.

Final Approval Given  Y  N By (EHS #) J.K.

SITE VISIT WORKSHEET

Permit Number: 2002-07-022624

Date Printed: August 7, 2002

Property Location: 2950 Cstle Butte Drive Lot 141

County: Douglas

Owner: Light House Custom Homes

SITE INFORMATION AS REPORTED BY ENGINEER:

PERC RATE:

Holes:

One 7 Two 7 Three 7 Four \_\_\_\_\_ Five \_\_\_\_\_ Six \_\_\_\_\_ Avg Rate 7 Sizing Rate 20

CIRCLE ONE:

Bedrock Encountered? Yes (No) If Yes, Type \_\_\_\_\_ Depth to Bedrock (ft) \_\_\_\_\_

Ground Water Encountered? Yes (No) If Yes, Depth to Groundwater (ft) \_\_\_\_\_

Ground Slope at Absorption Area (%) 5% to W

Max depth of disposal area (in) 56 (not to exceed depth of percolation test holes)

Min depth of disposal area (in) 22

SOIL CLASSIFICATION: Most prohibitive soil below bottom of bed (circle one)

- CL Clay (low-med plasticity) CH Clay (high plasticity) MH Silt
ML Silt ML-CL Silt & Clay SC Clayey Sand
SM-SC Silty Clayey Sand SM Silty Sand SW Sand, Well Graded
SP Sand, Poorly Graded GC Clayey Gravel GM-GC Silty Clayey Gravel
GM Silty Gravel BR Bedrock GW Gravel, Well Graded

FIELD OBSERVATIONS:

Field Observations Consistent with Engineer's Data: Yes No Just Pit Waived
IF NO, complete below (circle one)

Bedrock Encountered? Yes No If Yes, Type \_\_\_\_\_ Depth to Bedrock (ft) \_\_\_\_\_

Ground Water Encountered? Yes No If Yes, Depth to Groundwater (ft) \_\_\_\_\_

Ground Slope at Absorption Area (%) \_\_\_\_\_

Max depth of disposal area (in) \_\_\_\_\_ (not to exceed depth of percolation test holes)

Min depth of disposal area (in) \_\_\_\_\_

SOIL CLASSIFICATION:

- CL Clay (low-med plasticity) CH Clay (high plasticity) MH Silt
ML Silt ML-CL Silt & Clay SC Clayey Sand
SM-SC Silty Clayey Sand SM Silty Sand SW Sand, Well Graded
SP Sand, Poorly Graded GC Clayey Gravel GM-GC Silty Clayey Gravel
GM Silty Gravel BR Bedrock GW Gravel, Well Graded

CONTINUED ON THE NEXT PAGE

SITE VISIT WORKSHEET

Permit Number: 2002-07-022624

Date Printed: August 7, 2002

RECORD OF SITE VISITS:

(It is important to record any extra visits for billing purposes)

Visit 1 Date 8/9/2002 By (EHS #) 1555  
 Visit 2 Date \_\_\_\_\_ By (EHS #) \_\_\_\_\_  
 Visit 3 Date \_\_\_\_\_ By (EHS #) \_\_\_\_\_  
 Visit 4 Date \_\_\_\_\_ By (EHS #) \_\_\_\_\_


SPECIAL CONDITIONS

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

COMMENTS

Made field visit, found all parcels, No Wells within  
 100 ft. approved  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Signature TCHD Inspector: John Kleckner Date 8/9/2002



---

**CASTLE ROCK ENGINEERING INC.** 101 Briscoe Street, Unit A, Castle Rock, CO 80104 • Phone/Fax (303) 688-5151

---

**PREPARED FOR**

**LIGHTHOUSE CUSTOM HOMES  
P. O. BOX 708  
LITTLETON, CO 80160**

**SUBSURFACE INVESTIGATION  
AND  
PERCOLATION TESTING**

**OF**

**LOT 141  
KEENE RANCH SUBDIVISION  
DOUGLAS COUNTY, COLORADO**

**REPORT NO. 02-2730  
JULY 15, 2002**

# TABLE OF CONTENTS

DISCLAIMER .....	2
SCOPE OF WORK.....	2
SITE CONDITIONS.....	2
FOUNDATION REQUIREMENTS .....	2
LATERAL LOADS.....	2
SUBSURFACE DRAINAGE.....	2
FIELD AND LABORATORY INVESTIGATION .....	2
SUBSURFACE CONDITIONS .....	3
DESIGN AND DETAILS FOR SLAB ON GRADE CONSTRUCTION .....	3
SURFACE DRAINAGE.....	4
LIMITATIONS.....	4



## **DISCLAIMER**

*The parties specifically agree that Castle Rock Engineering, Inc. has not been retained nor will they render an opinion concerning any environmental issues, hazardous waste or any other known or unknown conditions that may be present on this site.*

## **SCOPE OF WORK**

This report presents the results of data obtained during the subsoil investigation of Lot 141, Keene Ranch Subdivision, Douglas County, Colorado. The purpose of this investigation is to test, analyze, and report the conditions of the soils encountered. These tests pertain to the suitable design and construction of an appropriate foundation for the proposed building and/or residences to determine the load-bearing capacities of the soil.

## **SITE CONDITIONS**

The site is currently vacant. It is our understanding that a single family home is planned to be built on this site.

## **FOUNDATION REQUIREMENTS**

A satisfactory type of foundation system will be continuous concrete footings. Footing foundations should bear on the undisturbed natural soils and below all organic material. All loose and disturbed soil shall be removed before pouring the concrete for the footings. These footings should be designed for a maximum soil bearing pressure of 2,000 pounds per square foot. Refer to foundation design for footing size verification. All continuous footings supporting perimeter concrete foundation walls should be at least 16 inches wide. Foundation walls should be well reinforced, a minimum of two No. 5, grade 60, top and bottom. We recommend reinforcement sufficient to span an unsupported distance of at least 10 feet. The exterior footings shall be a minimum of 3 feet below final grade for frost protection. Some movement may occur with this type of foundation system.

## **LATERAL LOADS**

Below grade walls must be designed for lateral loads. We recommend the walls be designed for an equivalent fluid pressure of 35 pound per cubic foot (pcf). The recommended design pressure does not include surcharge or hydrostatic loads. To reduce the risk of development of hydrostatic pressure, we recommend installation of an exterior or interior foundation drain as indicated on Figure 4.

## **SUBSURFACE DRAINAGE**

The installation of a foundation drainage system is required for any habitable space below grade level. See Perimeter Drain Detail, Figure 4, for a suggested method of installing this system

## **FIELD AND LABORATORY INVESTIGATION**

Two (2) exploratory test holes were drilled on July 9, 2002, at the site shown on the Location Map, Figure 1. This test hole was drilled with a 4-inch diameter auger. At specific intervals, the drilling

tools were removed from the test holes and soil samples were taken. A description of the soils encountered is shown on the Logs of Test Holes, Figure 2, and the Summary of Laboratory Testing, Table 1.

All soil samples were carefully inspected in the field during the drilling operation. These samples were classified in the laboratory through visual inspection and testing to determine the pertinent properties. The natural moisture content was obtained from relatively undisturbed drive samples of typical soils.

### **SUBSURFACE CONDITIONS**

The subsurface conditions encountered in the borings consisted of silty, clayey sand to the depths of borings, 20 feet. Free groundwater was not encountered in the borings at the time of drilling. The results of the swell consolidation and gradation tests are presented on Figure 3 through 3c.

### **DESIGN AND DETAILS FOR SLAB ON GRADE CONSTRUCTION**

The natural soils appear suitable for the support of exterior and interior concrete slabs. It is very important for the moisture to stay constant during the construction process. When sandy soils have an increase in moisture content, they may consolidate and settle, potentially lowering and cracking the concrete slab. When clayey soils are exposed to an increase in moisture content, they can increase in volume resulting in movement and possible cracking of the concrete slab. Experience with similar soil conditions has shown that the following details help prevent damage to a concrete slab. Experience with similar soil conditions has shown that the following details help prevent damage to a concrete slab:

1. The slab must be placed directly on undisturbed natural soils, or on recompact soil. Do not place a gravel layer beneath the concrete slab.
2. The floating slab must be separated from the foundation or utility lines to allow for independent movement of the slab. A positive slip joint must be provided at the junction between the slab and foundation walls.
3. Control joints must be provided in the slab to confine cracks to the joints and not in the visible are of the slab. Control joints must be one-third the thickness of the slab. The maximum slab area between control joists shall be 200 square feet. A maximum dimension of 16 feet in any direction is permitted.
4. A minimum void of 1½ inches shall be provided at the bottom of all non-bearing partitions. Drywall or paneling shall not be placed within 2 inches of the top surface of the slab, allowing space for upward movement of the slab.
5. If a hot water heating system is used, the piping should not be placed beneath the concrete floor slab. If a forced air furnace is used, a 2-inch flexible connection should be installed between the furnace and the duct.
6. The soils that will support the concrete slabs should be kept moist, but not wet, during construction.
7. If the builder or future owner provides decorative gravel or bark around the building, see Foundation Grading Detail, Figure 5, for an acceptable method of installation. This

method will prevent ponding of water near the foundation and provide for proper drainage away from the building.

### SURFACE DRAINAGE

The backfill soil around the building should be kept moist and well compacted to prevent future settling. Controlled puddling of the backfill soils is not allowed. For proper drainage, a slope of 10% (6 inches in first 5 feet) away from the foundation in all directions is required. This slope must be maintained for a minimum distance of 5 feet. The future owners are advised to immediately fill in any settled area near the building to eliminate containment of water. Downspouts must discharge onto four-foot long concrete splash blocks or into metal gutter extensions to direct water away from the house.

The future owners should be cautioned regarding the installation of a lawn adjacent to the foundation walls. Lawn irrigation can not be permitted within 5 feet of the foundation walls. Any watering adjacent to the foundation should be by hand and kept to a minimum.


### LIMITATIONS

In any soil investigation it is necessary to assume that the subsurface soil conditions do not vary greatly from the conditions encountered in our field and laboratory testing. Our experience has been that at times soil conditions do change and variations do occur and may become apparent at the time of excavation for the foundation system. If soil conditions are encountered which appear different from the test borings as presented in this report, it is requested that an engineer from this office be called to inspect the open excavation. This inspection service is not a part of this report.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by reputable geotechnical engineers practicing in this or similar localities. No warranty, expressed or implied, is made. We prepared the report as an aid in design of the proposed project.

Should you have any questions or if we may be further assistance in this matter, we are at your service.


CASTLE ROCK ENGINEERING, INC.




David E. Beasley, P.E.


dcc

ALL MEASUREMENTS  
ARE APPROXIMATE



- △ SOIL TEST HOLE FOR BUILDING
- SOIL PROFILE HOLE FOR ABSORPTION BED
- PERCOLATION TEST HOLE

 <p><b>CASTLE ROCK ENGINEERING, INC.</b></p>	<p><b>LOCATION MAP</b></p>	<p>DATE: 7/12/02</p>
	<p><i>Consulting Engineering</i></p> <p><i>Soil &amp; Percolation Test, Foundation &amp; Septic System Design</i></p>	<p>JOB NO. 02-2730</p>
		<p>FIG. NO. 1</p>



- SM-SAND, silty, sli clayey, loose to med dense, moist, brn to lt brn
- SC-SAND, v clayey, silty, v gravelly, v moist, brn to lt brn

NOTES:

1. No water was encountered during the drilling of the test holes
2.  Location of modified California barrel sample: (26/12) indicates that 26 blows with a 140# hammer, falling 30" were required to drive a 2.5" dia. sampler 12"
3.  Groundwater on Drill Date  
 Groundwater 24-48 hours later



LOG OF TEST HOLES


CASTLE ROCK ENGINEERING INC.

GEOTECHNICAL & STRUCTURAL CONSULTANTS


DATE: 7/12/02


JOB NO. 02-2730

FIG. NO. 2




Specimen Identification	Classification	DD (pcf)	MC (%)
TH # 1 @ 3'	SM-SAND, silty, sli clayey, loose to med dense, moist, brn to lt brn	103.6	3.9


	<b>SWELL-CONSOLIDATION TEST</b>	DATE: 7/15/02
	GEOTECHNICAL & STRUCTURAL CONSULTANTS	JOB NO. 02-2730
	CASTLE ROCK ENGINEERING INC.	FIG. NO. 3




Specimen Identification	Classification	DD (pcf)	MC (%)
TH # 1 @ 8'	SC-SAND, v clayey, silty, v gravelly v moist, brn to lt brn	112.9	6.4

	<b>SWELL-CONSOLIDATION TEST</b>	DATE: 7/15/02
	GEOTECHNICAL & STRUCTURAL CONSULTANTS	JOB NO. 02-2730
	<b>CASTLE ROCK ENGINEERING INC.</b>	FIG. NO. 3a

Hole No.	Depth (feet)	Moisture Content %	Dry Density pcf	140# Hammer Blows	Passing 200 sieve %	Swell (+) or Consol (-) %	Soil Description
TH #1	3'	3.9	103.6	20/9	16.0	-1.9	SM-SAND, silty, sli clayey, loose to med dense, moist, brn to lt brn
TH #1	8'	6.4	112.9	20/10	6.9	-0.6	SC-SAND, v clayey, silty, v gravely, v moist, brn to lt brn
BAG SAMPLE SPH	2'-7'	6.8	---	---	21.7	---	SC-SAND, v clayey, silty, med dense, v moist, lt brn
BAG SAMPLE SPH	7'-10'	6.1	---	---	10.0	---	SC-SAND, v clayey, silty, med dense v moist, gravely, brn to lt brn


	<b>SUMMARY OF LABORATORY TESTING</b>		DATE: 7/15/02
	GEOTECHNICAL & STRUCTURAL CONSULTANTS		JOB NO. 02-2730
	CASTLE ROCK ENGINEERING INC.		TABLE 1






BACKFILL AROUND THE FOUNDATION SHOULD BE MOISTENED AND COMPACTED AND THE FINAL GRADE SHOULD BE WELL SLOPED TO PRECLUDE PONDING OF RAINFALL, IRRIGATION WATER AND SNOW MELT ADJACENT TO FOUNDATION WALLS. CAUTION: DO NOT DIKE OR IMPEDE THE FLOW OF WATER AWAY FROM FOUNDATION WALLS WITH SOD, EDGING OR DECORATIVE GRAVEL AND POLYETHYLENE. DOWNSPOUTS AND SILL COCKS SHOULD DISCHARGE INTO SPLASH BLOCKS OR LONG EXTENSIONS.

FOOTING FOUNDATION SYSTEM

 <p><b>CASTLE ROCK ENGINEERING INC.</b></p>	<p>DRAIN SYSTEM BELOW GRADE &amp; BACKFILL DETAILS</p>	<p>DATE: 7/12/02</p>
	<p>GEOTECHNICAL &amp; STRUCTURAL CONSULTANTS</p>	<p>JOB NO. 02-2730</p>
	<p></p>	<p>FIG. NO. 4</p>



**DRAINAGE AROUND FOUNDATION WALL**

**CASTLE ROCK ENGINEERING INC.**

GEOTECHNICAL & STRUCTURAL CONSULTANTS

DATE: 7/12/02

JOB NO. 02-2730

FIG. NO. 5

**CASTLE ROCK ENGINEERING INC.** 101 Briscoe Street, Unit A, Castle Rock, CO 80104 • Phone/Fax (303) 688-5151

Lighthouse Custom Homes  
P. O. Box 708  
Littleton, CO 80160

Date: July 12, 2002  
Observation Date: July 10, 2002  
Job No.: 02-2730

At your request, we ran percolation tests at Lot 141, Keene Ranch Subdivision, Douglas County, Colorado on July 10, 2002 (refer to Fig. 1). We recommend that this site utilize a conventional leaching system.

Test results are as follows:


**Lot 141  
Keene Ranch Subdivision  
Douglas County, Colorado**

Percolation hole #1:	7
Percolation hole #2:	7
Percolation hole #3:	7
Average Perc Rate:	7

If you have any questions, please call.

CASTLE ROCK ENGINEERING INC.

Reviewed by:



David E. Beasley, P.E

*Tri County Health Department*  
*Percolation Test and Soils Data Form*

Property address Lot 141, Keene Ranch Subdivision, Douglas County, Colorado

Legal description \_\_\_\_\_

Property Owner:

Name Lighthouse Custom Homes

Address P. O. Box 708, Littleton, CO 80160

Phone (303) 901-6848

Note:

- Percolation Test Form, Site Plan and Grain Size Distribution Curve of the Sample must be submitted with this form.
- For all Lots < 5 acres the site plan must include the entire lot. Test locations must be accurately tied to lot corners or other permanent markers.

Saturation and Swelling

Date and time presoak water added:  
7/9/02

Amount of presoak added (gallons):  
FIVE GALLONS

Date and time percolation test started:  
7/10/02

Did water remain in hole after the overnight swelling period:

Hole 1  Yes  No

Hole 2  Yes  No

Hole 3  Yes  No

Percolation Rate Measure:

Hole 1 7

Hole 2 7

Hole 3 7

Average 7

Groundwater

Groundwater Encountered:  Yes  No

If yes, at what depth: N/A feet

Estimated depth to maximum seasonal water table if not encountered in profile: 20'

Is area believed to be subject to seasonal fluctuations which could result in a seasonal water table within 8' of surface?

Yes  No

Slope determination in absorption area: 5.0 %  
to the west (direction)

Bedrock

Bedrock Encountered:  Yes  No

If yes, bedrock encountered at N/A feet

Type of bedrock (if present):

Sandstone  Claystone  Siltstone

Other: \_\_\_\_\_

If present is bedrock fractured or weathered:


Yes  No

PROFILE HOLE INFORMATION (Cont.)  
 (Soils must be classified using Unified System ASTM D2487)




PROFILE HOLE LOG

SPH # 1

Blow Counts at Depth of Bed: 20/10  
 Atterberg Limits:  
 PL: \_\_\_\_\_  
 LL: \_\_\_\_\_  
 PI: \_\_\_\_\_



20/10  
Tests

-  SC-SAND, v clayey, v moist, drk brn
-  SC-SAND, v clayey, silty, med dense, v moist, lt brn
-  SC-SAND, v clayey, silty, med dense, v moist, gravelly, brn to lt brn

CERTIFICATION


TD 10'  
 DRY

I certify that the above information is correct and complete to the best of my knowledge and that all tests were performed in accordance with the provisions of Tri-County Health Department Regulation I-96 by myself or under my supervision.

*David Emerson Bessley*  
 Original Signature

7/23/02  
 Date

Castle Rock Engineering Inc.  
 101 Briscoe St. Unit A, Castle Rock, CO 80104  
 (303) 688-5151



**TRI-COUNTY HEALTH DEPARTMENT  
PERCOLATION TEST RESULT FORM**

JOB NO. 02-2730

Hole No.	Hole Depth (in.)	Length of Interval (min.)		Water Depth at Start of Interval (in.)	Water Depth at End of Interval (in.)	Drop in Water Level (in.)	Percolation Rate at Final Interval (min./in.)
1	58"	10	**	82.5000	72.5000	10.0000	1.0
		10	**	72.5000	69.5000	3.0000	3.3
		10		77.5000	75.0000	2.5000	4.0
		10		75.0000	73.5000	1.5000	6.7
		10		73.5000	72.0000	1.5000	6.7
		10		75.0000	71.5000	3.5000	2.9
							<b>7</b>
2	32"	10	**	222.0000	216.0000	6.0000	1.7
		10	**	228.5000	224.0000	4.5000	2.2
		10		224.0000	222.2500	1.7500	5.7
		10		222.2500	221.0000	1.2500	8.0
		10		224.0000	222.0000	2.0000	5.0
		10		222.0000	220.5000	1.5000	6.7
							<b>7</b>
3	55"	10	**	127.5000	117.0000	10.5000	1.0
		10		117.0000	113.2500	3.7500	2.7
		10		127.5000	121.5000	6.0000	1.7
		10		121.5000	117.5000	4.0000	2.5
		10		117.5000	114.5000	3.0000	3.3
		10		114.5000	113.0000	1.5000	6.7
							<b>7</b>
<b>Average Perc Rate</b>							<b>7</b>

**\*\* WATER ADDED**

\*FIELD NOTES SHALL BE RECORDED ON THIS FORM OR IN THIS FORMAT; TYPED COPIES OF FIELD RECORDS MAY BE SUBMITTED ON THIS FORM.

\*A FOUR HOUR TEST MUST BE CONDUCTED UNLESS (A) WATER REMAINS IN THE HOLE AFTER THE PRESOAK IN WHICH CASE ONE 30 MIN. INTERVAL IS SUFFICIENT, (B) THE FIRST 6" OF WATER SEEPS AWAY IN <30 MINUTES IN WHICH CASE A ONE-HOUR TEST OF 6 - 10 MINUTE TIME INTERVALS MAY BE USED, (C) THE TEST IS BEING CONDUCTED IN SAND (SW OR SP) IN WHICH CASE A ONE HOUR TEST OF 6 - 10 MINUTE TIME INTERVALS MAY BE USED, (D) THREE SUCCESSIVE WATER LEVEL DROPS DO NOT VARY BY MORE THAN 1/16 INCH IN WHICH CASE A TWO-HOUR TEST MAY BE CONDUCTED, (E) TEST IS IN DAWSON SANDS, IN WHICH CASE THE TEST MUST BE RUN A MINIMUM OF FOUR HOURS UNTIL THE LAST THREE SUCCESSIVE WATER LEVEL DROPS VARY BY LESS THAN 1/16 INCH.

HYDROMETER ANALYSIS

TIME READINGS

60MIN. 19MIN. 4MIN. 1MIN. #200


U.S. STANDARD SERIES

#100 #50 #40 #30

SIEVE ANALYSIS

CLEAR SQUARE OPENINGS

#16 #10 #8 #4 3/8" 3/4" 1.5" 3"



CLAY(PLASTIC) TO SILT(NON-P) FINE SAND MEDIUM COARSE FINE GRAVEL COARSE COBBLES

GRAVEL 0.2 % SAND 78.1 % SILT & CLAY 21.7 %

BAG SAMPLE OF SPH @ 2'-7'



CASTLE ROCK ENGINEERING INC.

GRADATION TEST RESULTS

GEOTECHNICAL & STRUCTURAL CONSULTANTS

DATE: 7/15/02

JOB NO. 02-2730

FIG. NO. 3b

HYDROMETER ANALYSIS

TIME READINGS

60MIN. 19MIN. 4MIN. 1MIN. #200


U.S. STANDARD SERIES

#100 #50 #40 #30 #16

SIEVE ANALYSIS

CLEAR SQUARE OPENINGS

#10 #8 #4 3/8" 3/4" 1.5" 3"



CLAY (PLASTIC) TO SILT (NON-P) FINE SAND MEDIUM COARSE FINE GRAVEL COARSE COBBLES

GRAVEL 2.8 % SAND 87.2 % SILT & CLAY 10.0 %

BAG SAMPLE OF SPH @ 7'-10'



CASTLE ROCK ENGINEERING INC.

GRADATION TEST RESULTS


GEOTECHNICAL & STRUCTURAL CONSULTANTS

DATE: 7/15/02


JOB NO. 02-2730

FIG. NO. 3c






LOT 141, KEENE RANCH



(SP.01) SITE PLAN  
1" = 50'

*Walt Styer*  
Aug 6, 02



PROPOSED RESIDENCE  
LOT 141, KEENE RANCH  
DOUGLAS COUNTY,  
COLORADO

**SUBMITTALS:**

curb cut-07/15/02

**REVISIONS:**


DATE: 07/02/02
SCALE: AS SHOWN
LA JOB #: 110101
SHEET
<b>SP1</b>